



am-clad

hygienic pvc wall cladding

NBS SPECIFICATION CLAUSE FOR AM-CLAD HYGIENIC 2.5mm COLOURS WITH PVC TRIMS

K13/160 Rigid sheet fine linings and panelling

To be read with Preliminaries/ General conditions.

TYPES OF LINING AND PANELLING

160 PROPRIETARY HYGIENIC PANELLING

AM-Clad high quality, hygienic PVC wall cladding system. The fully installed system is easy to clean and maintain and is water resistant.

- **Substrate:**

- Type Fair Fixed Brickwork / Blockwork
Plastered / Rendered Walls
12mm ply WBP Boarded out stud Partitions
Ceramic Tiles (check all tiles are soundly fixed)
Painted walls (subject to tape test)
- Preparation: Walls should be flat to a minimum of 3mm +or when measured over a 2 metre edge
- All areas to be clean, dry and fully degreased.
- Any porous surfaces should be sealed with a suitable diluted PVA.

- **Panels:**

- Supplier: AM-Clad Limited 10-14 Ward Street, Bradford, West Yorkshire, BD7 3PR
Telephone: +44 (0) 1274 578 051 Email: info@am-clad.com www.am-clad.com

- **Product reference:** AM-Clad Hygienic PVC Colours

- Board/ Panel type: Hygienic PVC sheet
- Thickness: 2.5mm
- Core material: UPVC.
- Panel Width: 1220mm wide
- Panel Heights: 2438mm (8') 2744mm (9') and 3048mm (10')
- Colours: See our updated colour range at am-clad.com and in the latest AM-Clad Specifiers Guide. Exact colours to be confirmed by Architect /Designer



am-clad

hygienic pvc wall cladding

- Moisture content at time of fixing: As recommended by fabricator to suit environmental conditions.
 - Edge treatment: Square.
Finish: Smooth satin finish.
 - Fire Rating: Meets BS EN 11925-2 Bs3d0: Class 0 when fully adhered to a non-combustible surface.
- **Installation:**
- Method of fixing: Trowel applied 2-part AM-Clad polyurethane adhesive.
 - Jointing: Use colour-matched Am-Clad 2-Part H-Divider Bars. Use Edge Trims to doors and abutments and transition trim to coved flooring. Trims to be kept to a minimum where possible. Refer to AM-Clad Installation Guide.
Corners: AM-Clad sheets to be heat treated with AM-Clad thermoformer to form internal and external angles. Alternatively, use AM-Clad colour matched internal and external corner trims.
Sealants: All exposed edges to be sealed with high quality foodsafe colour-matched silicone sealant.
Moisture content at time of fixing: All substrates to be dried to minimum of 16% WME (Wood Moisture Equivalent)
- **Included features:** EEC Food Hygiene Directive 64/483 Compliant.
- **Accessories:** Coved Skirtings if required.

GENERAL REQUIREMENTS

260 ENVIRONMENTAL CONDITIONS

- General requirements prior to starting work specified in this section: Building weathertight; wet trades completed and affected areas dried out.
- Temperature and humidity before, during and after fixing lining/ panelling: Maintained at levels approximating to those which will prevail after building is occupied.

FABRICATION/ FIXING/ FINISHING

310 ACCURACY OF FABRICATION

- Site dimensions: Take as necessary before starting fabrication
- Discrepancies with drawings: Report without delay and obtain instructions before proceeding.

340 HOLES/ CUT-OUTS IN LAMINATED PLASTICS VENEERS

- Internal corners: Formed to a radius, minimum 5 mm when not specified otherwise.
- Holes for fasteners: Formed slightly oversize.

350 FIXING LININGS AND PANELLING

- Setting out: Accurate, true to line and level, free from undulations and lipping, with lines and joints aligned, straight and parallel unless specified otherwise.
- Movement allowance: Adequate for future moisture and temperature movement of boards.
- Fixing of panels: Secure, to prevent pulling away, bowing, or other movement during use.
- Methods of fixing and fasteners: As section Z20 unless specified otherwise.
- Trims: Wherever possible, to be in unjointed lengths between angles or ends of runs.
Running joints: Where unavoidable, submit proposals for location and method of jointing.
Angle joints: Mitred, unless specified otherwise.



am-clad
hygienic pvc wall cladding

DELIVERY

400 Do not deliver components to site and do not remove protective packaging / coverings until immediately before required for fixing.

Stack boards and panels flat on bearers and separated by spacers where necessary to prevent damage to or from projections.

Keep components and completed linings /panelling clean and dry. Protect from physical damage until practical completion.